

# Valentine Corporation Bid Schedule for Week Ending May 17, 2024

5/10/24

Bid Date & Time	Estimator	Location	Owner & Project Name	Project Number	Description	Engineer's Estimate	Days to Complete	Minority / GFE	Pre-Bid Meeting	Add
<b>May 13th - 17th</b>										
Tuesday 05/14/24 @ 2 pm	BV	Hayward	Alameda County Flood Control & Water Conservation District - Eden Landing & Besco Pump Station Outfall Structure & Flap Gates Rehabilitation	F262	Implementing water pollution control plan, job site management; designing, installing, maintaining, and removing de-watering systems; replacing six (6) flap gates; upsizing existing storm drain pipe; replacing a portion of the existing concrete headwall and wingwall; furnishing, placing and compacting trench backfill; furnishing, placing and compacting asphalt concrete.	\$862,000	470 CD	NONE	<b>Mandatory Virtual Pre-Bid 4/30 @ 11 AM</b>	
Tuesday 05/14/24 @ 2 PM	BV	Corte Madera	Sanitary District No. 2 of Marin County-2024 Paradise Pump Station Rehabilitation Project	23-202	Installation of new pumps, discharge piping, valves, flow meter, supports, anchorage, VFD's, PLC, backup pump controller, valve vault, access hatch, ventilation improvements, gas system monitoring improvements and lighting.	\$8,825,000	450 WD	None	Non-Mandatory Pre-Bid/Site Walk Thurs. 4/11 @ 10 AM	3
Thursday 05/16/24 @ 11:30AM	BV	Napa	County of Napa - Mt. Veeder Road MPM 3.99	RDS -23-23	Replacing the damaged road with a 142' long cast-in-place drilled hole pile supported retaining wall. The retaining wall will restore lateral support to the outboard edge of roadway and allow fill placement where approximately 60' of the westbound travel lane	\$816,000	50 WD	None	None	2
Thursday 05/16/24 @ 2 PM <i>ELECTRONIC</i>	BV	Millbrae	City of Millbrae - Sludge Thickener & Disgester No. 2 Rehabilitation		Thickener tank blasting, and epoxy lining of sludge thickener tank, Furnish sludge thickener mechanical and electrical equipment, Thickener startup, testing, training, and turnover, Digester No. 2 gas dome, center pipe, and manhole hatch abrasive blasting and coating, Repair for cracks using epoxy or grout, Spalling repair	\$853,081	150 WD	None	<b>Mandatory Pre-Bid 4/30 @ 10 AM LB</b>	2
Friday 05/17/24 @ 2 PM <i>Electronic</i>	BV	Marin	County of Marin, 170 to 190 Redwood Drive Storm Damage Repair	2023-11	84-ft precast concrete lagging wall with steel soldier piles, new culvert installation, swale gradation, installation of a rip rap apron for the new culvert, pavement grinding, reconstruction of the roadway structural section in the failed area, paving 4" HMA over 8" of class 2 AB, and guardrail installation.	\$720,000	60 WD	DBE 12%	None	2
<b>May 20th - 24th</b>										
Wednesday 05/21/24 @ 2 PM <i>ELECTRONIC</i>	BV	Greenbrae	REBID - County of Marin, DPW - Hal Brown Bridge @ Pathway Project	MCP 2024-01	New prefabricated bridge, boardwalk and pathway.	\$1,393,150	120 WD	None	<b>Mandatory Pre-Bid Weds. 5/14 @ 2 PM</b>	
Wednesday 05/21/24 @ 2 PM	BV	Vacaville	City of Vacaville - Lagoon Valley Park Pedestrian Bridge Replacement	CIP 1001 / 840164	Installation of a new truss type prefabricated pedestrian bridge, installation of new foundation elements, and all other ancillary work.	\$430,000	50 WD	None	None	1
Wednesday 05/22/24 @ 11 AM	BV	Vacaville	City of Vacaville - Ulatis Creek Bank Repair Phase #1	CIP 983 / 820333	Clearing and Grubbing, excavation, construction of soldier pile retaining wall, placement of rock slope protection, relocation and installation of irrigation, and re vegetation.	\$1,400,000	75 WD	None	None	
Wednesday 05/22/24 @ 2 PM <i>ELECTRONIC</i>	BV	Napa	Caltrans - Napa Co. Calistoga at 2.5 Miles South of Lake County Line	04-0Q8304	Soldier pile, Conc backfill, HMA, timber lagging, and MGS.	\$1,300,000	345 WD	None	None	
<b>May 27th - May 30st</b>										
Tuesday 05/28/24 @ 2 PM	BV	Bay Point	Contra Costa County PWD - Bay Point Trash Capture Installation	7517-6W7079	Installing a prefabricated Debris Separating Baffle Box (DSBB) on Willow Pass Road at Alves Lane in the Bay Point area. Work includes temporary water diversion and dewatering, roadway and structure excavation, temporary shoring, installation of DSBB unit and manhole, reconstruction of roadway and slurry seal, and replacing roadway striping.	\$927,500	40 WD	None	Non Mandatory Virtual Pre-Bid 5/13 @ 10 AM	
Thursday 05/30/24 @ 11 AM	BV	Pope Valley	County of Napa - Sewer Lift Station A Tank Replacement Project	LB 22-03	Furnishment & install new 50,000 gallon concrete sewer tank w/Internal & external ladder, 10,000 gallon polyethylene overflow tank, associated inlet/outlet piping, overflow & drain piping, all associated fittings, appurtenances, level floats, radar level sensors, connections to existing pump suction piping; temporary bypass piping to the overflow tank used while the new concrete tank is being construction; modifications to existing sump pit piping; new overflow piping connecting to existing Baker Tank w/backfill, compaction, site restoration, keystone retaining wall; demolition of existing tank & foundation; demolition of existing fence; startup & testing of all equipment; replacement of approximately 1000 ft of six-inch Asbestos Concrete sewer force main w/eight-inch fused HDPE pipe.	\$1,793,000	120 WD	DBE	<b>Mandatory Pre-Bid 5/8 @ 9:30 AM=LB</b>	
<b>June 3rd - 7th</b>										
Thursday 06/06/24 2 PM <i>Electronic</i>	BV	Marin	County of Marin, DPW - Sir Francis Drake Blvd MP 20.97 Slide Repair Project	2019-22	Constructing two separate cast-in-drilled-hole concrete retaining walls with a pile cap and tiebacks. One wall will be approximately 101'in length, the other will be approximately 148' in length. Culvert replacement, installation of rock slope protection, and roadway paving.	\$1,400,000	50 WD	DBE 16%	None	2